

CENTRAL SECRETARIAT CLUB (Regd.)
7-10, Park Street, Talkatora
Road, New Delhi-110001

EC/MC/CSC/QUOTATION/25-26/56

Date – 25/08/2025

QUOTATION

Online Item Rate Quotations are invited for the underneath work from registered firms in categories of class 4 & 5 from CPWD/ MES / Experienced Firms in the similar nature of work & can be seen at web site csclub.in & to be uploaded at E-mail ID of club centralsecretariatclub24@gmail.com on or before 03/09/2025 at 3.00 PM and shall be downloaded at 3.30 PM on 03/09/2025.

Name of Work - SITC of false ceiling with Gypsum Board at billiards room and old secretary room Central Secretariat Club.

S. No.	Description of Item	Qty.	Unit	Rate	Amount	DSR-2023
1	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with :					12.45

CENTRAL SECRETARIAT CLUB (Regd.)
7-10, Park Street, Talkatora
Road, New Delhi-110001

1.1	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks).	85.00	Sqm			
2	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	85.00	Sqm			
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	85.00	Sqm			
4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.					
4.1	Two coats	85.00	Sqm			
5	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content.					
5.1	With water thinnable cement primer on wall surface having VOC content	85.00	Sqm			
Total						A
	Modified estimated cost after using correction factor on DSR-2023 on account of GST @ 0.973 vide O.M dated 08.08.2024					
Total						
Total						
6	Credit of old dismantled steel bar received after dismantling at site all complete as per direction of Engineer-in-charge.	15.00	Kg.	-	-	AR
Total						
Say						

Terms and conditions

- 1) The work shall be carried out as per CPWD specification Amended UpToDate.
- 2) No Tools & Plant shall be given by club.
- 3) Nothing extra shall be paid on account of taxes and levies etc.
- 4) EMD for Rs 2000/- shall be deposited in favour of General Secretary, Central Secretariat club in form of FDR/Bank Guarantee & to be deposited physically as well as uploaded online and is refundable after completion of work.
- 5) All dismantle false ceiling material shall have to be removed from club premises.

CENTRAL SECRETERIAT CLUB (Regd.)
7-10, Park Street, Talkatora
Road, New Delhi-110001

- 6) Credit to dismantle false ceiling has to be given by the participants.
- 7) Bad workmanship shall not be accepted at any cost.
- 8) The work shall be completed in 7 days time after award of work.


Rakesh Kumar
General Secretary
Central Secretariat Club

Copy to;

1. All Executive Members / managing Committee Members
2. DoP & T members
3. Notice Board